

FOR CONTRACTORS & SUPPLIERS ONLY FOR PAYMENT FOR WORK OR SUPPLIES ACTUALLY MEASURED			
First & Final Bill			
Cash Book Voucher No.		Date-	
Name of Contractor or supplier :	M/s. Shree Krishna Builders Jaipur		
Name of Work :-	Plumbing Installation and MTC work at Govt. Nehru hostel Mansarovar, Sanganer, Jaipur		
Serial No. of this bill :	First & Final Bill	No. and date of the last bill-	Not Applicable
Reference to work order or Agreement :	0511 Dt. 05-11-2023		
Agreement No.	48/2024-25		
Date of written order to commence work :	05/11/2024		
St. date of Start :	12/11/2024		
St. date of completion :	09/08/2025		
Date of actual completion of work :	14/08/2025		
Date of measurement :	15/09/2025		

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub-head)	Remarks
			1.0	Rewiring of light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III) virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, round tiles, 1.2 mm thick MS box with earth terminal, 6 A switch, 3 pin ceiling rose/holder / 3 way connector , 3.0 mm thick ISI marked (IS:2036-1995) phenolic laminated sheet, Al.alloy / Cadmium plated iron/ brass screws, cup washers, making connections, testing etc. as required. For specification of copper Conductor, Phenolic Laminated sheet's & Electrical/ Wiring accessories refer Chapter E - 04, E - 05 & E - 07 For additional technical parameters of product / work refer Annexure 'A' attached with this BSR				1.5
P. point	52.00	52.00		Short point (up to 3 mtr.)	256.00	13312.00	13312.00	1.5.1
P. point	48.00	48.00		Medium point (up to 6 mtr.)	472.00	22656.00	22656.00	1.5.2
P. point	52.00	52.00		Long point (up to 10 mtr.)	662.00	34424.00	34424.00	1.5.3
			2.0	Rewiring of 3/5 pin 6 amp. Light plug point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III) virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, 1.2 mm thick MS box with earth terminal of required size, 6 A switch, 3/5 pin 6 A socket, 3.0 mm thick ISI marked (IS:2036-1995) phenolic laminated sheet, Al.alloy / Cadmium plated iron/ brass screws, cup washers, making connections, testing etc. as required. For specification of copper Conductor, Phenolic Laminated sheet's & Electrical/ Wiring accessories refer Chapter E - 04, E - 05 & E - 07 For additional technical parameters of product / work refer Annexure 'A' attached with this BSR				1.7
P. point	102.00	102.00		On board	136.00	13872.00	13872.00	1.7.1

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub-head)	Remarks
Each	8.00	8.00	3.0	P & F ISI marked (IS:3854) 6 amp. flush type non modular switch with CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material including cutting hole in tile and making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	23.00	184.00	184.00	7.1
				EXTRA ITEM/S				
Each	2.00	2.00	E-01	Minimum lumen output 2500 lm Post top Luminarie	5075.00	10150.00	10150.00	
Each	4.00	4.00	E-02	6 A 3/5 pin shuttered socket	107.00	428.00	428.00	
Each	5.00	5.00	E-03	6/16 A shuttered socket	176.00	880.00	880.00	
Each	5.00	5.00	E-04	Providing & Fixing of modular type lockable feature socket duly made out of unbreakable and fire retardant vergin poly carbonate with brass terminals and captive screws & silver alloy contact tip with IP-20 rating, including all as per pre approved by Engineer in charge, making connections, testing etc. as required. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR	345.00	1725.00	1725.00	
Each	4.00	4.00	E-05	6 A 3/5 pin shuttered socket	107.00	428.00	428.00	
Each	5.00	5.00	E-06	6/16 A shuttered socket	176.00	880.00	880.00	
				Grand Total Rs.		84448.00	84448.00	
				Tender Premium @ 5.11%	5.11%	4315.29	4315.29	
Rs. 15231.00				<<<<<< Sum of Extra Items (including Tender Premium)				
				Payable Amount Rs.		103994.29	103994.29	
				Less Amount Paid vide Last Bill Rs.		0.00	0.00	
				Net Payable Amount Rs.		103994.29	103994.29	