

DEVIATION STATEMENT

Name of Work :- Electric Repair and MTC work at Govt. Ambedkar hostel Ambamata, Govardhanvilas, Udaipur

Name of Contractor or supplier : M/s Seema Electrical Udaipur

Serial No. of this bill : Second Running Bill

Agreement No. 48/2024-25

[illegible]

ITEM No.	Description	Unit	Qty as per Work Order	Rate	Amt as per Work Order Rs.	Qty Executed	Amt as per Executed Rs.	Excess Qty	Excess Amt Rs.	Saving Qty	Saving Amt Rs.	REMARKS/ REASON.
	ground/surface/recess including riveting, soldering, saddles, making connection with GI/Cu purity >95% thimble etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .											
15	8 SWG G.I. (Hot Dipped) Wire Providing & Fixing of BEE Star rated copper wounded double ball bearing capacitor start, aluminium body & Metallic blade ceiling fan Conforming to all the performance requirements laid down in IS 374:2019 including all amendments, as applicable ; & Carry BIS licensing (i.e. ISI marking) with down rod up to 80 cm with secondary support safety cable (steel rope) , cotter pin with 3 x 1.5 sq.mm pvc insulated flexible copper conductor making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	Mtr.	100	20.00	2000.00	35	700.00			65	1300.00	14.6.8
16	1200 mm Sweep BEE 1 Star rated (service value >=4.0 to < 4.5) Providing & Fixing of IP20 SMD Mid Power LED batten	Each	10	1890.00	18900.00	12	22680.00	2	3780.00			15.7.1

[illegible]

[illegible]

ITEM No.	Description	Unit	Qty as per Work Order	Rate	Amt as per Work Order Rs.	Qty Executed	Amt as per Executed Rs.	Excess Qty	Excess Amt Rs.	Saving Qty	Saving Amt Rs.	REMARKS/ REASON.
	Double Door (Metal / Glazed)Distribution board with Metal end box made out from Galvanized steel / CRCA sheet not less than 1.2 mm thick conforming to IS-8623-1 & 3 / IEC 61439- 1 & 3, powder painted complete with reversible door (for double door DB only)100 amp. insulated copper bus bar/shorting link , copper neutral link, copper earth link , color coded interconnecting wire set of suitable rating and din bar,masking sheet, making internal DB terminations with copper lugs, Ferrules, detachable gland plate, including making connections, testing etc. as required. OEM shall have submit NABL / CPRI / ERDA accredited lab type test reports & All as per pre approved by Engineer in charge. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR											
	Metal door (single phase) IK-09 and IP-43 with Metal end box											
	8 Way (8+2)	Each	8	2184.00	17472.00	25	54600.00	17	37128.00			6.10.1.3
	<u>Extra Items (With Premium)</u>											
E-01	6 A 3/5 pin shuttered socket	Each		107.00		4	428.00	4	428.00			
E-02	6/16 A shuttered socket	Each		176.00		5	880.00	5	880.00			
E-03	Providing & Fixing of modular type lockable feature	Each		345.00		5	1725.00	5	1725.00			

ITEM No.	Description	Unit	Qty as per Work Order	Rate	Amt as per Work Order Rs.	Qty Executed	Amt as per Executed Rs.	Excess Qty	Excess Amt Rs.	Saving Qty	Saving Amt Rs.	REMARKS/ REASON.
	socket duly made out of unbreakable and fire retardant vergin poly carbonate with brass terminals and captive screws & silver alloy contact tip with IP-20 rating, including all as per pre approved by Engineer in charge, making connections, testing etc. as required. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR											
E-04	6 A 3/5 pin shuttered socket	Each		107.00		4	428.00	4	428.00			
E-05	6/16 A shuttered socket	Each		176.00		5	880.00	5	880.00			
	Grand Total Rs.				119014.00		254648.00		137918.00		2284.00	
	Add Tender Premium (22.22%)				26445.00		56583.00		30645.00		508.00	
	Grand Total including Tender Premium Rs.				145459.00		311231.00		168563.00		2792.00	
	Overall Excess With Respect to the Work Order Amount Rs.								165772.00			
	Percentage of Excess %								113.96%			