

CONTRACTOR BILL

Item Description Unit Quantity Rate Amount BSR

1 Rewiring of light point/ fan point/ exhaust fan point/ call bell point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III) virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, round tiles, 1.2 mm thick MS box with earth terminal, 6 A switch, 3 pin ceiling rose/holder / 3 way connector , 3.0 mm thick ISI marked (IS:2036-1995) phenolic laminated sheet, Al.alloy / Cadmium plated iron/ brass screws, cup washers, making connections, testing etc. as required. For specification of copper Conductor, Phenolic Laminated sheet's & Electrical/ Wiring accessories refer Chapter E - 04, E - 05 & E - 07 For additional technical parameters of product / work refer Annexure 'A' attached with this BSR 1.5

Short point (up to 3 mtr.) P. point 50 256 12800 1.5.1

Medium point (up to 6 mtr.) P. point 50 472 23600 1.5.2

Long point (up to 10 mtr.) P. point 50 662 33100 1.5.3

2 Rewiring of 3/5 pin 6 amp. Light plug point with 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper conductor 1.1 kV grade and 1.5 sq. mm nominal size FR PVC insulated unsheathed flexible copper earth conductor 1.1 kV grade (IS:694) in recessed ISI marked MMS (IS:9537 P - III) virgin material PVC conduit & it's ISI marked (IS:3419-1988) accessories, 1.2 mm thick MS box with earth terminal of required size, 6 A switch, 3/5 pin 6 A socket, 3.0 mm thick ISI marked (IS:2036-1995) phenolic laminated sheet, Al.alloy / Cadmium plated iron/ brass screws, cup washers, making connections, testing etc. as required. For specification of copper Conductor, Phenolic Laminated sheet's & Electrical/ Wiring accessories refer Chapter E - 04, E - 05 & E - 07 For additional technical parameters of product / work refer Annexure 'A' attached with this BSR 1.7

On board P. point 100 136 13600 1.7.1

3 P & F ISI marked (IS:3854) 6 amp. flush type non modular switch with CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material including cutting hole in tile and making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 10 23 230 7.1

4 P & F ISI marked (IS :3854) 16 amp. flush type non modular switch CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material including cutting hole in tile and making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 30 50 1500 7.2

5 Providing & Fixing of of 3/5 pin 6 amp. flush type non modular socket made out from industrial grade Polycarbonate or fire resistant ABS material, brass terminal with Porcelain based back cover & captive screws including cutting hole in tile and making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 10 33 330 7.10

6 Providing & Fixing of 3/6 pin 16 amp flush type non modular socket made out from Industrial grade Polycarbonate or fire resistant ABS material, brass terminal with Porcelain based back cover & captive screws including cutting hole in tile and making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 10 78 780 7.11

7 Providing & Fixing of ISI marked (IS:371) 6 amp surface type 3 pin ceiling rose with CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material, brass terminal & captive screws including making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 10 30 300 7.12

8 Providing & Fixing of ISI marked (IS:1258) batten/angle lamp holder with CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material, brass terminal & captive screws including making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 10 30 300 7.13

9 Providing & Fixing of IS 11037:1984 marked non modular socket size flush type 180 watt rotary minimum 5 step fan regulator with CM/L no. printed and made out from industrial grade Polycarbonate or fire resistant ABS material including making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR . Each 33 219 7227 7.21

10 Providing and fixing of power plug point with non modular accessories as per PWD specification for electrical Works with Galvanized box of 1.2 mm thick with earth terminal with suitable size phenolic laminated sheet (IS : 2036 - 1995) cover including cost of 16 amp. Switch (IS :3854) and 3/6 pin 16 amp. socket outlet making connection , testing , etc. as required. . For specification of Wiring accessories refer Chapter E - 07 related item & For additional technical parameters of product / work refer Annexure 'A' attached with this BSR Each 44 303 13332 7.36

11 S&F following sizes (dia.) of ISI marked virgin material MMS (IS:9537 P - III) PVC conduit along with ISI marked (IS:3419-1988) accessories as required in recess including cutting the wall, covering conduit and making good the same as required. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR 1.4

20 mm R. mtr. 300 40 12000 1.4.1

25 mm R. mtr. 100 56 5600 1.4.2

12 Supplying and drawing FR PVC insulated & unsheathed flexible copper conductor as per PWD specification for electrical Works with ISI marked (IS:694) and as per IS 8130 : 2013 of 1.1 kV grade . Wire should be made from 99.90 % purity copper, class 2 stranding in acc. to IS:8130/IEC 60228 for lower watt loss , oxygen free for less chances of oxidization, insulation PVC type A/C/D , flame retardant as per IS 10810-53, better amperage rating as per IS:3961 part 5, in existing surface or recessed PVC/ MS conduit/casing capping making connections with Copper Lugs of suitable size, Ferrules, testing etc. as required. OEM Must have its own in house NABL lab setup for all testing facilities for wires. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR 4.1

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub- head)	Remarks
Set	15.0	15.0	13	Plate Earthing as per IS:3043 with Hot dipped G.I. Earth plate of size 600mm x 600mm x 6.0mm by embodying 3 to 4 mtr. below the ground level with 20 mm dia. G.I.	5733.0	85995	85995	14.2

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub- head)	Remarks
				'B' class watering Pipe ,including all accessories like nut, bolts, reducer, nipple, wire meshed funnel, and Heavy duty weather proof poly-propylene earth pit chamber with lockable Jam free lid suitable for safe working load 5000 Kg or more of size Top Dia. 225 to 260 mm, Bottom Dia 300 to 350 mm. and Height 250 to 300 mm. and embodying the pipe complete with alternate layers salt and coke/ charcoal, testing of earth resistance for value of 5 ohms or less as required & must record by engineer in charge during site visit and ensure to enter in measurment book.All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .				
			14	Supply & Laying following size earth wire in horizontal or vertical run in ground/surface/recess including riveting, soldering, saddles, making connection with GI/Cu purity purity >95% thimble etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .			14.6	
Mtr.	35.0	35.0	15	8 SWG G.I. (Hot Dipped) Wire Providing & Fixing of BEE Star rated copper wounded double ball bearing capacitor start, aluminium body & Metallic blade ceiling fan Conforming to all the performance requirements laid down in IS 374:2019 including all amendments, as applicable ; & Carry BIS licensing (i.e. ISI marking) with down rod up to 80 cm with secondary support safety	20.0	700	700	14.6.8 15.7

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub- head)	Remarks
				cable (steel rope) , cotter pin with 3 x 1.5 sq.mm pvc insulated flexible copper conductor making connection testing etc. as required. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .				
Each	12.0	12.0		1200 mm Sweep BEE 1 Star rated (service value ≥ 4.0 to < 4.5) Providing & Fixing of IP20 SMD Mid Power LED batten type integrated light fixture made from Powder coated Extruded aluminium housing with in built driver , System lumen efficacy $\geq$ 110 lm/Watt output, internal surge protection of 2.5 KV with Short & Open circuit protection ,THD $<$ 10% , P. F. ≥ 0.95 , CRI > 80 , life time of minimum 50000 Burning Hours with , 70% of intial Lumen maintaned till life ends , CCT 3000°K / 4000°K / 5700°K /6000°K/6500°K (As per ANSI Bin) , Maximum power consumption should not more than the specified rating and Fixture shall be of BIS standard and trade mark certificate (T.C.). Manufactures Word Mark/ Name Engraved/ Embossing/ Screen printing on housing. OEM must have its own in house NABL lab setup for all testing facilities for LED fixtures. (LM79 & LM80) certificate / Report from OEM shall be submitted. All as per pre approved by Engineer in charge. For additional technical parameters of products/ work , refer Annexure "A" attached with this BSR .	1890.0	22680	22680	15.7.1
			16					17.1
Each	78.0	78.0		1170mm(+/-10%) LED batten with min. lumen output 2200 lm	492.0	38376	38376	17.1.1

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub- head)	Remarks
			17	Providing & Fixing of 240/415 V AC MCB with positive isolation of 10 kA breaking capacity (B/ C/D tripping characteristic as per type of load and site requirement) 4 KV impulse withstand voltage, ISI marked IS 8828(1996) / conforming to IEC 60898-1 2002, IEC 60947-2, low watt losses, trip free mechanism , energy limiting of class 3 as per IEC, minimum phase termination capacity of 35sq.mm. , conductor line load reversibility , IP 20 contact protection and fitted in existing distribution board/sheets, minimum electrical operation 20,000 upto 20 A rating and 10,000 upto 63 A, 5000 for 80 A & above rating including making connections, testing etc. as required. OEM shall have submit NABL / CPRI / ERDA accredited lab type test reports & All as per pre approved by Engineer in charge. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR				6.1
				Single pole MCB (With B/C curve tripping Characteristics)			6.1.1	
Each	88.0	88.0		6 A to 32 A rating	187.0	16456	16456	6.1.1.2
				Double pole MCB(With B/C curve tripping Characteristics)				6.1.2
Each	35.0	35.0		50/63 A rating	900.0	31500	31500	6.1.2.4
			18	Providing & Fixing of Recessed/surface mounting heavy duty horizontal type Double Door (Metal / Glazed)Distribution board with Metal end box made out from Galvanized steel / CRCA sheet not less then 1.2 mm thick conforming to IS-8623-1 & 3 / IEC 61439- 1 & 3, powder painted complete with reversible door (for double door				6.1

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub- head)	Remarks
				DB only)100 amp. insulated copper bus bar/shorting link , copper neutral link, copper earth link , color coded interconnecting wire set of suitable rating and din bar,masking sheet, making internal DB terminations with copper lugs, Ferrules, detachable gland plate, including making connections, testing etc. as required. OEM shall have submit NABL / CPRI / ERDA accredited lab type test reports & All as per pre approved by Engineer in charge. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR				
				Metal door (single phase) IK-09 and IP-43 with Metal end box				6.10.1
Each	25.0	25.0		8 Way (8+2)	2184.0	54600	54600	6.10.1.3
	0	0		Extra Items (With Premium)	0	0	0	
Each	4.0	4.0	E-01	6 A 3/5 pin shuttered socket	107.0	428	428	
Each	5.0	5.0	E-02	6/16 A shuttered socket	176.0	880	880	
				Providing & Fixing of modular type lockable feature socket duly made out of unbreakable and fire retardant vergin poly carbonate with brass terminals and captive screws & silver alloy contact tip with IP-20 rating, including all as per pre approved by Engineer in charge, making connections, testing etc. as required. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR				
Each	5.0	5.0	E-03		345.0	1725	1725	
Each	4.0	4.0	E-04	6 A 3/5 pin shuttered socket	107.0	428	428	
Each	5.0	5.0	E-05	6/16 A shuttered socket	176.0	880	880	
				Grand Total Rs.		254648	254648	
				Tender Premium @ 22.22%	22.22%	56583	56583	
Sum of Extra Items (including Tender Premium): Rs. 5306								
				Payable Amount Rs.		311231	311231	

Unit	Quantity executed (or supplied) since last certificate	Quantity executed (or supplied) upto date as per MB	S. No.	Item of Work supplies (Grouped under "sub-head" and "sub work" of estimate)	Rate	Upto date Amount	Amount Since previous bill (Total for each sub- head)	Remarks
				Less Amount Paid vide Last Bill Rs.		0.00	0.00	
				Net Payable Amount Rs.		311231	311231	