

DEVIATION STATEMENT

Name of Work :- Electric Repair and MTC work at Govt. Ambedkar hostel Ambamata, Govardhanvilas, Udaipur

Name of Contractor or supplier : M/s Seema Electrical Udaipur

Serial No. of this bill : Second Running Bill

Agreement No. 48/2024-25

[illegible]

[illegible]

[illegible]

ITEM No.	Description	Unit	Qty as per Work Order	Rate	Amt as per Work Order Rs.	Qty Executed	Amt as per Executed Rs.	Excess Qty	Excess Amt Rs.	Saving Qty	Saving Amt Rs.	REMARKS/ REASON.
	breaking capacity (B/ C/D tripping characteristic as per type of load and site requirement) 4 KV impulse withstand voltage, ISI marked IS 8828(1996) / conforming to IEC 60898-1 2002, IEC 60947-2, low watt losses, trip free mechanism , energy limiting of class 3 as per IEC, minimum phase termination capacity of 35sq.mm. , conductor line load reversibility , IP 20 contact protection and fitted in existing distribution board/sheets, minimum electrical operation 20,000 upto 20 A rating and 10,000 upto 63 A, 5000 for 80 A & above rating including making connections, testing etc. as required. OEM shall have submit NABL / CPRI / ERDA accredited lab type test reports & All as per pre approved by Engineer in charge. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR Single pole MCB (With B/C curve tripping Characteristics) 6 A to 32 A rating Double pole MCB(With B/C curve tripping Characteristics) 50/63 A rating	Each	50	187.00	9350.00	88	16456.00	38	7106.00			6.1.1.2
18	Providing & Fixing of Recessed/surface mounting heavy duty horizontal type	Each	10	900.00	9000.00	35	31500.00	25	22500.00			6.1.2.4

ITEM No.	Description	Unit	Qty as per Work Order	Rate	Amt as per Work Order Rs.	Qty Executed	Amt as per Executed Rs.	Excess Qty	Excess Amt Rs.	Saving Qty	Saving Amt Rs.	REMARKS/ REASON.
	Double Door (Metal / Glazed)Distribution board with Metal end box made out from Galvanized steel / CRCA sheet not less than 1.2 mm thick conforming to IS-8623-1 & 3 / IEC 61439- 1 & 3, powder painted complete with reversible door (for double door DB only)100 amp. insulated copper bus bar/shorting link , copper neutral link, copper earth link , color coded interconnecting wire set of suitable rating and din bar,masking sheet, making internal DB terminations with copper lugs, Ferrules, detachable gland plate, including making connections, testing etc. as required. OEM shall have submit NABL / CPRI / ERDA accredited lab type test reports & All as per pre approved by Engineer in charge. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR											
	Metal door (single phase) IK-09 and IP-43 with Metal end box											
	8 Way (8+2)	Each	8	2184.00	17472.00	25	54600.00	17	37128.00			6.10.1.3
	<u>Extra Items (With Premium)</u>											
E-01	6 A 3/5 pin shuttered socket	Each		107.00		4	428.00	4	428.00			
E-02	6/16 A shuttered socket	Each		176.00		5	880.00	5	880.00			
E-03	Providing & Fixing of modular type lockable feature	Each		345.00		5	1725.00	5	1725.00			

ITEM No.	Description	Unit	Qty as per Work Order	Rate	Amt as per Work Order Rs.	Qty Executed	Amt as per Executed Rs.	Excess Qty	Excess Amt Rs.	Saving Qty	Saving Amt Rs.	REMARKS/ REASON.
	socket duly made out of unbreakable and fire retardant vergin poly carbonate with brass terminals and captive screws & silver alloy contact tip with IP-20 rating, including all as per pre approved by Engineer in charge, making connections, testing etc. as required. For additional technical parameters of product / work refer Annexure 'A' attached with this BSR											
E-04	6 A 3/5 pin shuttered socket	Each		107.00		4	428.00	4	428.00			
E-05	6/16 A shuttered socket	Each		176.00		5	880.00	5	880.00			
	Grand Total Rs.				119014.00		254648.00		137918.00		2284.00	
	Add Tender Premium (22.22%)				26445.00		56583.00		30645.00		508.00	
	Grand Total including Tender Premium Rs.				145459.00		311231.00		168563.00		2792.00	
	Overall Excess With Respect to the Work Order Amount Rs.								165772.00			
	Percentage of Excess %								113.96%			